

## GENERAL CONSTRUCTION NOTES:

INSTALLATION AND CONSTRUCTION SHALL CONFORM TO THE DEPARTMENT OF TRANSPORTATION STANDARDS SPECIFICATIONS SECTIONS APPLICABLE, STANDARD PLANS DATED AND EFFECTIVE FOR THE CURRENT YEAR, AND ANY SPECIAL MUNICIPALITY CODE PROVISIONS.

1. THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES IS APPROXIMATE. THE SUBCONTRACTOR SHALL DETERMINE THE LOCATION AND DEPTH OF ALL UTILITIES INCLUDING THOSE NOT SHOWN ON PLANS AND VERIFY ALL JOB SITE CONDITIONS, HAND EXCAVATE FOUNDATION UNTIL CLEAR OF ALL SUBSTRUCTURES AND PROTECT ALL FACILITIES DURING CONSTRUCTION. SUBCONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS FOR UNDERGROUND UTILITY REMOVAL OR RELOCATION WITH RESPECTIVE UTILITY OWNERS AS MAY BE REQUIRED SUFFICIENTLY IN ADVANCE TO PREVENT DELAY IN OPERATIONS.
2. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND UTILITIES ENCOUNTERED IN AREAS WHERE EXCAVATIONS ARE INDICATED AND SHALL REPAIR ANY SUCH DAMAGE AT OWN EXPENSE. WHERE UTILITY LINES MUST BE MAINTAINED UNDER STRUCTURE, THEY SHALL BE PROPERLY SLEEVED THROUGH FOUNDATION.
3. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR REPLACEMENT OR REPAIR OF ANY DAMAGE CAUSED BY THEM OR THEIR SUBCONTRACTORS.
4. THE SUBCONTRACTOR SHALL OBTAIN AND PAY FOR ALL REQUIRED PERMITS AND NOTIFY ALL UTILITIES AND THE CITY AT LEAST 72 HOURS IN ADVANCE OF CONSTRUCTION.
5. THE SUBCONTRACTOR SHALL CALL THE TRANSPORTATION TRAFFIC DIVISION, FIVE (5) DAYS PRIOR TO THE START OF WORK FOR A TRAFFIC CONTROL PLAN APPOINTMENT
6. THE SUBCONTRACTOR IS REQUIRED TO SUBMIT A WEEKLY SCHEDULE PRIOR TO START OF WORK EACH WEEK. (NO EXCEPTIONS)
7. POLE MOUNTED DETECTOR AND EQUIPMENT LOCATIONS SHALL BE AS DEPICTED ON SITE PLAN. THE SUBCONTRACTOR SHALL VERIFY EQUIPMENT FIELD LOCATIONS WITH THE ACS IMPLEMENTATION MANAGER (301) 357-9403 OR LOCAL AND/OR EXCAVATION AUTHORITY AND ACS PRIOR TO INSTALLATION.
8. THE SUBCONTRACTOR SHALL SUPPLY AND INSTALL ALL CONDUCTORS NECESSARY FOR THE INTENDED OPERATION AS NOTED ON THESE PLANS, NEC AND ALL APPLICABLE MUNICIPALITY CODES.
9. PROVIDE ANCHOR BOLT NUT COVERS IF REQUIRED DUE TO EXTERIOR INSTALLATION
10. ALL PULLBOXES AND COVERS SHALL BE CONCRETE OR PVC AS REQUIRED BY THE MUNICIPALITY. ALL PULLBOXES SHALL BE NO. 5 UNLESS OTHERWISE NOTED OR REQUIRED BY THE MUNICIPALITY.
11. ALL CONCRETE FORMS ARE TO BE INSPECTED BY LOCAL AUTHORITIES BEFORE CONCRETE IS PLACED.
12. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING AND COORDINATION WITH THE SERVING (ELECTRICAL) UTILITY COMPANY AND PAY REQUIRED FEES FOR SERVICE CONNECTIONS.
13. THE SUBCONTRACTOR TO OBTAIN A NO FEE ENCROACHMENT PERMIT FROM THE CITY PRIOR TO COMMENCEMENT OF WORK. ALL WORK SHALL BE INSPECTED BY CITY FORCES. AT COMPLETION OF PROJECT CONTACT THE CITY ENGINEER 24 HOURS PRIOR TO COMPLETION OF WORK
14. THE SUBCONTRACTOR IS TO BUILD AND MAINTAIN A CONSTRUCTION BARRICADE, TRAFFIC CONTROLS SHALL BE PER THE LATEST TMUTCD STANDARDS TO INCLUDE THE ARROW BOARD. NO LANE CLOSURES DURING PEAK TRAFFIC HOURS.
15. ALL SUBCONTRACTORS TO PROVIDE LIABILITY INSURANCE AND WORKERS COMPENSATION BENEFITS IN ACCORDANCE WITH STATE LAW FOR ALL WORKERS AND AGENTS WHO WILL BE ON THE SITE AT ANY TIME WHILE PERFORMING WORK ON THIS PROJECT. ALL WORK SHALL BE IN ACCORDANCE WITH NEC, ALL LOCAL, STATE AND FEDERAL CODES, ORDINANCES AND ANY APPLICABLE AMENDMENTS.

16. ALL DEBRIS, EXCESS MATERIAL, ETC. IS TO BE REMOVED BY THE SUBCONTRACTOR BY THE END OF THE JOB. JOB TO BE LEFT SUFFICIENTLY CLEAN AS TO WARRANT CITY APPROVAL.
17. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMITS, FEES AND INSPECTIONS AS MAY BE REQUIRED FOR COMPLETION OF THE JOB AS PER ALL GOVERNING AGENCIES.
18. THE SUBCONTRACTOR TO PROVIDE COST ESTIMATE FOR ALL WORK SHOWN ON DRAWINGS AND WORK NORMALLY REQUIRED TO CARRY OUT THE DESIGN INTENT OF THESE DRAWINGS.
19. DRAWINGS ARE NOT TO BE SCALED. WORK SHALL BE GOVERNED BY DIMENSION ONLY. DISCREPANCIES BETWEEN THE DRAWINGS AND/OR THE EXISTING SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF ACS IMMEDIATELY.
20. P.R.C. EQUIPMENT SHALL NOT BE INSTALLED ON MEDIANS LESS THAN FIVE FEET (5') IN WIDTH.
21. P.R.C. RELATED EQUIPMENT SHALL NOT BE INSTALLED WITHIN FIVE FEET (5') OF FIRE HYDRANT.
22. P.R.C. RELATED EQUIPMENT SHALL NOT BE INSTALLED WITHIN FOUR FEET (4') OF ADA RAMPS.
23. SUBCONTRACTOR SHALL SUPPLY AS-BUILT DRAWINGS TO ACS ENGINEERING DEPARTMENT WITHIN THIRTY (30) DAYS OF CONSTRUCTION COMPLETION.
24. SUBCONTRACTOR SHALL COMPLETE A "RLC POST CONSTRUCTION INSTALLATION ACCEPTANCE FORM" FOR EACH RLC INSTALLED. COMPLETED FORMS SHALL BE FORWARDED TO ACS CONSTRUCTION DEPARTMENT.
25. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE RESPECTIVE OWNERS AND OTHER AGENCIES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTACT:
  - \* GAS COMPANY
  - \* WATER DISTRICT
  - \* PHONE COMPANY
  - \* CABLE COMPANY
  - \* LOCAL AND/OR STATE EXCAVATION AUTHORITY

**SPECIFIC CONSTRUCTION NOTES:**

1. THE SUBCONTRACTOR SHALL INSTALL ALL SUBSTRUCTURES ACCORDING TO LOCAL GOVERNING AGENCY FROST LINE REQUIREMENTS WHERE APPLICABLE.
2. THE SUBCONTRACTOR SHALL MODIFY ALL SIDEWALKS WHERE NECESSARY, IN COMPLIANCE WITH THE ADA STANDARDS, TO ALLOW ACCESS FOR HANDICAP PEDESTRIAN PASSAGE.

## INDEX OF PLANS

<u>SHEET NUMBER</u>	<u>LOCATION/DESCRIPTION</u>
SIG 1	GENERAL NOTES
SIG 2	SITE PLAN
SIG 3	LOOP INSTALLATION DETAILS
SIG 4	SINGLE LINE DIAGRAM
SIG 5	CAMERA UNIT TERMINAL STRIP WIRING DETAILS
SIG 6	FLASH UNIT TO CAMERA POLE WIRING DETAILS
SIG 7	PELCO POLE DETAILS
SIG 8	CAMERA UNIT/DUAL FLASH CONFIGURATION



12410 MILESTONE CENTER  
DRIVE  
4TH FLOOR  
GERMANTOWN, MD 20876  
PHONE (301) 357-9403



**RAMEY KEMP**  
-- -- --  
**ASSOCIATES, INC.**  
Transportation Engineers  
6808 Farington Place, Suite 100  
Raleigh, North Carolina 27609  
919-872-8116 Tel. 919-878-6416 Fax.  
[www.rameykemp.com](http://www.rameykemp.com)



SR 1511 (Dawson Street)  
at  
South Street

Division 5                      Wake County                      Raleigh

PLAN DATE:	Dec 2008
------------	----------

REVIEWED BY:	
--------------	--

RKA PROJ. NO.:	08232 (040)
----------------	-------------

## REVISIONS

INIT.	DATE
-------	------

SEAL

SIGNATURE	DATE
IC. INVENTORY NO.	05-0942

2 Phase  
Pre-timed  
(Raleigh Signal System)

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated July 2006, "Standard Specifications for Roads and Structures" dated July 2006 and all applicable sections of the latest version of the generic Project Special Provisions. The PSP can be accessed at the following website:  
"http://www.ncdot.org/doh/preconstruct/traffic/ltss/"
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Pavement markings are existing.
4. Contractor to remove existing red light camera unit and loops and install new equipment as shown on this plan.

LEGEND

PROPOSED	EXISTING
	N/A
N/A	

SIGN I.D.

PROPOSED	EXISTING
(A) No Right Turn Sign (R3-1)	(A) No Right Turn Sign (R3-1)
(B) No Left Turn Sign (R3-2)	(B) No Left Turn Sign (R3-2)
(C) Right Arrow "ONLY" Sign (R3-5R)	(C) Right Arrow "ONLY" Sign (R3-5R)
(D) Left Arrow "ONLY" Sign (R3-5L)	(D) Left Arrow "ONLY" Sign (R3-5L)
(E) "DO NOT ENTER" Sign (R5-1)	(E) "DO NOT ENTER" Sign (R5-1)

TABLE OF OPERATION				
SIGNAL FACE	PHASE			
	Ø 6	Ø 4 + 8	F	L
41, 42, 43	G	R	Y	
61, 62	R	G	R	
81, 82	G	R	Y	
P41, P42	DW	W	DRK	
P61, P62	W	DW	DRK	
P63, P64	W	DW	DRK	
P81, P82	DW	W	DRK	

SIGNAL FACE I.D.


Denotes L.E.D.

	12"		16"
41, 42, 43		P41, P42	
61, 62		P61, P62	
81, 82		P63, P64	
		P81, P82	

2070L TIMING CHART				
FEATURE	PHASE			
	4	6	8	
Min Green 1 *	7	10	7	
Extension 1 *	0.0	0.0	0.0	
Max Green 1 *	-	-	-	
Yellow Clearance	3.3	3.8	3.0	
Red Clearance	2.4	1.9	2.8	
Walk 1 *	7	7	7	
Don't Walk 1	13	14	12	
Seconds Per Actuation *	-	-	-	
Max Variable Initial *	-	-	-	
Time Before Reduction *	-	-	-	
Time To Reduce *	-	-	-	
Minimum Gap	-	-	-	
Recall Mode	PED/MAX	-	PED/MAX	
Vehicle Call Memory	-	-	-	
Dual Entry	-	-	-	
Simultaneous Gap	ON	ON	ON	

\* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.


LOOP LOCATION DETAIL



Red Light Camera Installation - Site Plan

Prepared for:  250 Greenfield Plaza, Garner, NC 27529	SR 1511 (Dawson Street) at South Street	SEAL 
Prepared in the offices of: <b>RAMEY KEMP ASSOCIATES, INC.</b> Transportation Engineers 5808 Farlington Place, Suite 100 Raleigh, North Carolina 27609 919-872-5115 Tel. 919-878-5416 Fax. www.rameykemp.com	Division 5 Wake County Raleigh PLAN DATE: Dec 2008 REVIEWED BY: PREPARED BY:  RKA PROJ. NO.: 08232 (040) REVISIONS INIT. DATE 12-22-2008	SIG. INVENTORY NO. 05-0942

PHASING DIAGRAM




PHASING DIAGRAM DETECTION LEGEND

	DETECTED MOVEMENT
	UNDETECTED MOVEMENT (OVERLAP)
	UNSIGNALIZED MOVEMENT
	PEDESTRIAN MOVEMENT

RED LIGHT CAMERA LEGEND

Video Detection Camera	
Camera Unit	
Auxiliary Flash Assembly	
No. 5 Pullbox	
Power Pedestal	



CONDUIT PLAN  
(NOT TO SCALE)

CONDUIT SCHEDULE

LETTER	CONDUIT SIZE	CONDUIT CONSTRUCTION	TYPE OF SERVICE	EQUIPMENT SERVICED	CABLE QUANTITY	CABLE DETAILS
(A)	2"	PVC	COMMS	LOOPS 1, 2, 3, 4, 5, 7	6	(5)
(A1)	2"	PVC	COMMS	LOOPS 3, 4, 7	3	(5)
(B)	2"	PVC	COMMS	DUAL AUX FLASH UNIT	2	(4)
(C)	2"	PVC	POWER	DUAL AUX FLASH UNIT	6	(1)
(D)	2"	PVC	POWER	CAMERA UNIT POWER, RED/YELLOW PHASE CONTROL	3	(3) (1)
(E)	2"	PVC	POWER	GS-II UNIT	3	(3) (9) (1)
(F)	2"	PVC	COMMS	GS-II UNIT	2	(4) (6) (5) (1) (4A)
(G)	2"	PVC	COMMS	TO D-MARC LOCATION	1	(4A)

CABLE SCHEDULE

- 1 #14 AWG THHN
- 2 #12 AWG THHN
- 3 #10 AWG THHN
- 4 IMSA 40-2, 3 PAIR 19AWG w/ POLYETHYLENE JACKET (COMMS CABLE)
- 5 CAT-5e (BELDEN 7919A OR EQUIVALENT)
- 6 IMSA 50-2, 12 AWG
- 7 IMSA 51-7, 14 AWG
- 8 12 STRAND FIBER OPTIC CABLE
- 9 RG-59 VIDEO CABLE

NOTES


- 1 ACS TO PROVIDE CAMERA POLE AND CAMERA UNIT, SUBCONTRACTOR TO PROVIDE PELCO FOUNDATION. POLES SHALL BE FIELD LOCATED AND SHALL BE 36" MINIMUM FROM FACE OF CURB TO CENTER OF BASE. SEE DETAIL. LOCATION OF EQUIPMENT SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- 2 INSTALL TO LOCAL AND NEC SPECIFICATIONS
- 3 EACH POLE SHALL BE GROUNDED WITH #10 SOLID GROUND WIRE AND 10' GROUND ROD.
- 4 CONTRACTOR SHALL HAND DIG POLE FOUNDATION FOR ACS CAMERA OR FLASH UNIT POLES.
- 5 CONDUIT SHALL BE INSTALLED BY MEANS OF TRENCHING, TRENCHING SHALL BE IN ACCORDANCE TO CURRENT DOT STANDARD SPECIFICATIONS
- 6 CONTRACTOR SHALL MODIFY EXISTING 120VAC SERVICE, A DUPLEX OUTLET SHALL BE INCLUDED FOR ACCESS BY DOT PERSONNEL.
- 7 INSTALL NEW PULL BOX - SEE GENERAL NOTES #10, DWG. 2.0.
- 8 CONTRACTOR TO CLEAN UP DEBRIS AROUND WORK AREA AND RESTORE LANDSCAPE.
- 9 INSTALL IN-LINE FUSE HOLDERS RATED AT 20 AMPS FOR POWER.
- 10 INSTALL IN-LINE FUSE HOLDERS RATED AT 5 AMPS FOR PHASE CONDUCTORS.
- 11 INSTALL IN-LINE FUSE HOLDERS RATED AT 15 AMPS FOR EACH AUX FLASH POWER.
- 12 CONTRACTOR SHALL REPAIR AND REPLACE SIDEWALK IN KIND AS REQUIRED TO INSTALL EQUIPMENT AND CONDUITS.









[illegible]




## Red Light Camera Installation - Flash Unit to Camera Pole Wiring Details




1 - PLAN - BASE PLATE  
1 1/2"=1'-0"



2 - PLAN - FOUNDATION  
1 1/2"=1'-0"





3 - ELEVATION  
1 1/2"=1'-0"



4 - ELEVATION  
N.T.S.  
FOR REFERENCE

- NOTES:
1. ALL CONCRETE SHALL BE 28 DAY COMPRESSIVE STRENGTH  $f_c = 4000$  PSI.
  2. ALL REINFORCING STEEL SHALL BE ASTM 615, GRADE 60.
  3. THE PLACEMENT OF CONCRETE AND RE-BAR SHALL CONFORM TO THE REQUIREMENTS OF ACI 318 (LATEST EDITION).
  4. ALL ANCHOR BOLTS SHALL BE A-307 OR A-36 GRADE STEEL.
  5. CONTRACTOR SHALL PROTECT EXCAVATIONS FROM INCLEMENT WEATHER UNTIL CONCRETE HAS BEEN POURED.
  6. FOUNDATION MAY BE USED FOR PELCO GS-11 CAMERA OR AUXILIARY FLASH UNIT.
  7. CONTRACTOR TO VERIFY BOLT PROJECTION IN FIELD BEFORE INSTALLATION OF SHAFT.
  8. CONTRACTOR MAY SHIFT LOCATION OF TIES AS NECESSARY TO AVOID CONFLICT WITH CONDUIT.
  9. CAMERA FOUNDATION SHALL BEAR IN SOIL SUITABLE FOR 2,000 PSF BEARING CAPACITY. SHOULD UNSTABLE MATERIAL BE ENCOUNTERED AT THE BOTTOM OF THE EXCAVATION, THE FOUNDATION DEPTH MAY BE EXTENDED TO FIRM MATERIAL.

REV.	DESCRIPTION	DATE




**MCKIM & CREED**  
1730 Varsity Drive, Suite 500  
Raleigh, North Carolina 27606  
Phone: (919)233-8091, Fax: (919)233-8031  
www.mckimcreed.com



**PELCO GS-11 REDLIGHT CAMERA  
INSTALLATION**  
REINFORCED CONCRETE BASE  
SR 1511 (DAWSON STREET)  
@ SOUTH STREET

DATE: DECEMBER 2008	SCALE: AS NOTED	MAC FILE NUMBER: S7
MCE PROJ. # 1093-0027	HORIZONTAL: AS NOTED	DRAWING NUMBER: S7
DRAWN: [Signature]	VERTICAL: NA	
CHECKED: [Signature]		
PROJ. MGR. [Signature]		
STATUS: ISSUED FOR REVIEW		

SUBCONTRACTOR MUST NOTIFY THE BELOW LISTED AGENCY AT  
LEAST THREE (3) WORKING DAYS PRIOR TO COMMENCEMENT OF  
NORTH CAROLINA ONE CALL CENTER.  
1-800-632-4949



## Red Light Camera Installation - Camera Unit/Dual Flash Configuration



12410 MILESTONE CENTER  
DRIVE  
4TH FLOOR  
GERMANTOWN, MD 20876  
PHONE: (301) 357-9403



**RAMEY KEMP**  
-- -- --  
**ASSOCIATES, INC.**  
Transportation Engineers  
6806 Farinnden Place, Suite 100  
Raleigh, North Carolina 27609  
319-872-5116 Tel. 319-878-6416 Fax.  
[www.rameykemp.com](http://www.rameykemp.com)



SR 1511 (Dawson Street)  
at  
South Street

Division 5                      Wake County                      Raleigh

PLAN DATE:	Dec 2008
------------	----------

REVIEWED BY:	
--------------	--

PREPARED BY: [REDACTED]	RKA PROJ. NO.: 08232 (040)
-------------------------	----------------------------

REVISION	INIT.	DATE


SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

SIG. INVENTORY NO.	05-0942
--------------------	---------